

07/21/00
JC813 U.S. PTO

JC813 U.S. PTO
09/627147

07/21/00

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

Inventorship.....Cohen et al.
Applicant.....Microsoft Corporation
Attorney's Docket No.MS1-532US
Title: Shape and Animation Methods and Systems Using Examples

TRANSMITTAL LETTER AND CERTIFICATE OF MAILING

To: Commissioner of Patents and Trademarks,
Washington, D.C. 20231

From: Lance R. Sadler (Tel. 509-324-9256; Fax 509-323-8979)
Lee & Hayes, PLLC
421 W. Riverside Avenue, Suite 500
Spokane, WA 99201

The following enumerated items accompany this transmittal letter and are being submitted for the matter identified in the above caption.

1. Specification—title page, plus 49 pages, including 46 claims and Abstract
2. Transmittal letter including Certificate of Express Mailing
3. 14 Sheets Formal Drawings (Figs. 1-19) Figs. 7-10, 12-14, 16-19 in color
4. 2 Extra Copies of Color Figs. 7-10, 12-14 & 16-19
5. Petition Under 37 CFR 1.84(a)(2)
6. Fee Transmittal
7. Check in the amount of \$130.00
8. Return Post Card

Large Entity Status ☒

Small Entity Status ☐

Date: 7/21/00

By: 

Lance R. Sadler
Reg. No. 38,605

CERTIFICATE OF MAILING

I hereby certify that the items listed above as enclosed are being deposited with the U.S. Postal Service as either first class mail, or Express Mail if the blank for Express Mail No. is completed below, in an envelope addressed to The Commissioner of Patents and Trademarks, Washington, D.C. 20231, on the below-indicated date. Any Express Mail No. has also been marked on the listed items.

Express Mail No. (if applicable) EL624352269

Date: 7/21/2000

By: 

Lori A. Vierra

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

APPLICATION FOR LETTERS PATENT

**Shape and Animation Methods and Systems Using
Examples**

Inventor(s):

Michael F. Cohen

Charles F. Rose, III

Peter-Pike J. Sloan

ATTORNEY'S DOCKET NO. ms1-532us

TECHNICAL FIELD

This invention relates to the fields of computer graphics and computer animation. More particularly, the invention concerns methods and systems for creating or blending animated forms and/or motions.

BACKGROUND

Modern animation and modeling systems enable artists to create high-quality content, but provide limited support for interactive applications. Although complex forms and motions can be constructed either by hand or with motion or geometry capture technologies, once they are created, they are difficult to modify, particularly at runtime.

The magic of computer graphics as seen in many current movies and computer games comes at a cost. Creating geometric forms that are used to generate synthetic characters, and animating the characters to bring them to life requires either highly skilled artists and/or sophisticated capture devices. Both are expensive and, in the case of highly skilled artists, rare.

At this time, a variety of 3D scanning methodologies are available that can capture shapes that exist in the real world. Motion capture technologies are also capable of recording complex performances. One drawback of these capture systems is the cost that is incurred in their purchase and operation. Another limitation of capture devices is that they are restricted to recording shapes and motions that can be observed and that actually exist (e.g., such systems cannot capture the motion of a dinosaur). In contrast to the scanning devices, highly skilled artists have the advantage of being able to model complex existing shapes, as well as imaginary shapes and animations.

1 Both of these means of creating shapes and animations are limited in the
2 same way. In particular, neither has a simple means of automatically modifying
3 the shapes and animations once they have been created. It would be highly
4 desirable for current systems to be able to automatically modify a shape or
5 animation for two reasons. First, in scripted settings, such as films, automatic
6 modification makes it easier to avoid redundancy. For instance, an entire colony
7 of different looking ants could be automatically created from a few distinct ants.
8 In addition, the ants' motion could automatically adapt to changes in their mood or
9 to the terrain they are walking on. Second, in non-scripted interactive runtime
10 settings, such as games, it is not possible to anticipate all shapes and animations
11 that will be needed when the game is played. Thus, most games simply try to
12 reuse the closest fitting model or motion for the situation. One solution to the
13 above problems is to create more shapes and animations. Unfortunately, this
14 approach is very costly.

15 Accordingly, this invention arose out of concerns associated with
16 improving modern animation and modeling systems.

17 18 SUMMARY

19 Methods and systems that are suitable for leveraging existing forms and
20 motions to automatically generate variations are described. The methods and
21 systems are particularly well suited for generating variations at run time or "on the
22 fly". In the described embodiment, methodologies are presented for efficient
23 runtime interpolation or blending between multiple forms or multiple motion
24 segments. Interpolation provides a way to leverage artist-generated source
25

1 material. Radial basis functions provide mathematical support for the
2 interpolation.

3 In the described embodiment, example forms or motions are provided. The
4 forms or motions can be created by artists, or through geometry or motion capture
5 technologies. The described system generates a continuous range of forms termed
6 a “shape” or a continuous range of motions termed a “verb”. Shape interpolation
7 methodology can also be applied to articulated figures to create smoothly skinned
8 figures that deform in natural ways. The runtime interpolation of the forms or
9 motions runs fast enough to be used in interactive applications such as games.

10 11 **BRIEF DESCRIPTION OF THE DRAWINGS**

12 The file of this patent contains at least one drawing executed in color.
13 Copies of this patent with color drawing(s) will be provided by the Patent and
14 Trademark Office upon request and payment of the necessary fee.

15 Fig. 1 is a block diagram of an exemplary computer system that is suitable
16 for use with the described embodiments.

17 Fig. 2 is a block diagram of an exemplary system in which the inventive
18 methodologies can be employed.

19 Fig. 3 is a diagram that illustrates an exemplary abstract space and is useful
20 in understanding some of the concepts behind the inventive embodiments.

21 Fig. 4 is a flow diagram that describes steps in a method in accordance with
22 the described embodiments.

23 Fig. 5 is a flow diagram that describes steps in a method in accordance with
24 the described embodiments.

1 Fig. 6 is an illustration that is useful in understanding some of the concepts
2 behind the inventive interpolation methods of the described embodiments.

3 Fig. 7 is a graph that illustrates linear and radial basis portions of a cardinal
4 basis function in accordance with an example that is given.

5 Fig. 8 is a graph that illustrates cardinal basis functions and a scaled sum
6 function for a particular degree of freedom in accordance with the Fig. 7 example.

7 Fig. 9 is a color picture that describes exploration of abstract space that can
8 reveal problems involved with the described interpolation.

9 Fig. 10 is a color picture that describes pseudo-examples that can be used to
10 re-parameterize abstract space to address the problems revealed and illustrated in
11 Fig. 9.

12 Fig. 11 is a flow diagram that describes steps in a method in accordance
13 with the described embodiment.

14 Fig. 12 is a color picture that illustrates simple transformation blending that
15 leads to or exhibits shrinking about the joints.

16 Fig. 13 is a color picture that illustrates example forms that are warped into
17 a cononical pose.

18 Fig. 14 is a color picture that illustrates naïve transform blending versus
19 interpolated blending.

20 Fig. 15 is a flow diagram that describes steps in a method in accordance
21 with the described embodiment.

22 Fig. 16 is a color picture that illustrates examples and pseudo-examples in
23 accordance with the described embodiment.
24
25

1 Fig. 17 is a color picture that illustrates exemplary motions in accordance
2 with the described embodiment. In the figure, health increases as y increases and
3 slope of the surface ranges from sloping to left to right.

4 Fig. 18 is a color picture that illustrates exemplary motions in accordance
5 with the described embodiment. In the figure, knowledge increases from left to
6 right and happiness increases from bottom to top.

7 Fig. 19 is a color picture that provides more detail of the characters of Figs.
8 17 and 18.

9 DETAILED DESCRIPTION

10 Overview

11 Modern animation and modeling systems enable artists to create high-
12 quality content, but provide limited support for interactive applications. Although
13 complex forms and motions can be constructed either by hand or with motion or
14 geometry capture technologies, once they are created, they are difficult to modify,
15 particularly at runtime.
16

17 Interpolation or blending provides a way to leverage artist-generated
18 source material. Presented here are methodologies for efficient runtime
19 interpolation between multiple forms or multiple motion segments. Radial basis
20 functions provide key mathematical support for the interpolation. Once the
21 illustrated and described system is provided with example forms and motions, it
22 generates a continuous range of forms referred to as a "shape" or a continuous
23 range of motions referred to as a verb.

24 Additionally, shape interpolation methodology is applied to articulated
25 figures to create smoothly skinned figures that deform in natural ways. The

runtime interpolation of the forms or motions runs fast enough to be used in interactive applications such as games.

Exemplary Operating Environment

Fig. 1 is a high level block diagram of an exemplary computer system 130 in which the described embodiments can be implemented. Various numbers of computers such as that shown can be used in the context of a distributed computing environment. These computers can be used to render graphics and process images in accordance with the description given below.

Computer 130 includes one or more processors or processing units 132, a system memory 134, and a bus 136 that couples various system components including the system memory 134 to processors 132. The bus 136 represents one or more of any of several types of bus structures, including a memory bus or memory controller, a peripheral bus, an accelerated graphics port, and a processor or local bus using any of a variety of bus architectures. The system memory 134 includes read only memory (ROM) 138 and random access memory (RAM) 140. A basic input/output system (BIOS) 142, containing the basic routines that help to transfer information between elements within computer 130, such as during start-up, is stored in ROM 138.

Computer 130 further includes a hard disk drive 144 for reading from and writing to a hard disk (not shown), a magnetic disk drive 146 for reading from and writing to a removable magnetic disk 148, and an optical disk drive 150 for reading from or writing to a removable optical disk 152 such as a CD ROM or other optical media. The hard disk drive 144, magnetic disk drive 146, and optical disk drive 150 are connected to the bus 136 by an SCSI interface 154 or some

1 other appropriate interface. The drives and their associated computer-readable
2 media provide nonvolatile storage of computer-readable instructions, data
3 structures, program modules and other data for computer 130. Although the
4 exemplary environment described herein employs a hard disk, a removable
5 magnetic disk 148 and a removable optical disk 152, it should be appreciated by
6 those skilled in the art that other types of computer-readable media which can
7 store data that is accessible by a computer, such as magnetic cassettes, flash
8 memory cards, digital video disks, random access memories (RAMs), read only
9 memories (ROMs), and the like, may also be used in the exemplary operating
10 environment.

11 A number of program modules may be stored on the hard disk 144,
12 magnetic disk 148, optical disk 152, ROM 138, or RAM 140, including an
13 operating system 158, one or more application programs 160, other program
14 modules 162, and program data 164. A user may enter commands and
15 information into computer 130 through input devices such as a keyboard 166 and a
16 pointing device 168. Other input devices (not shown) may include a microphone,
17 joystick, game pad, satellite dish, scanner, or the like. These and other input
18 devices are connected to the processing unit 132 through an interface 170 that is
19 coupled to the bus 136. A monitor 172 or other type of display device is also
20 connected to the bus 136 via an interface, such as a video adapter 174. In addition
21 to the monitor, personal computers typically include other peripheral output
22 devices (not shown) such as speakers and printers.

23 Computer 130 commonly operates in a networked environment using
24 logical connections to one or more remote computers, such as a remote computer
25 176. The remote computer 176 may be another personal computer, a server, a

1 router, a network PC, a peer device or other common network node, and typically
2 includes many or all of the elements described above relative to computer 130,
3 although only a memory storage device 178 has been illustrated in Fig. 1. The
4 logical connections depicted in Fig. 1 include a local area network (LAN) 180 and
5 a wide area network (WAN) 182. Such networking environments are
6 commonplace in offices, enterprise-wide computer networks, intranets, and the
7 Internet.

8 When used in a LAN networking environment, computer 130 is connected
9 to the local network 180 through a network interface or adapter 184. When used
10 in a WAN networking environment, computer 130 typically includes a modem 186
11 or other means for establishing communications over the wide area network 182,
12 such as the Internet. The modem 186, which may be internal or external, is
13 connected to the bus 136 via a serial port interface 156. In a networked
14 environment, program modules depicted relative to the personal computer 130, or
15 portions thereof, may be stored in the remote memory storage device. It will be
16 appreciated that the network connections shown are exemplary and other means of
17 establishing a communications link between the computers may be used.

18 Generally, the data processors of computer 130 are programmed by means
19 of instructions stored at different times in the various computer-readable storage
20 media of the computer. Programs and operating systems are typically distributed,
21 for example, on floppy disks or CD-ROMs. From there, they are installed or
22 loaded into the secondary memory of a computer. At execution, they are loaded at
23 least partially into the computer's primary electronic memory. The invention
24 described herein includes these and other various types of computer-readable
25 storage media when such media contain instructions or programs for implementing

1 the steps described below in conjunction with a microprocessor or other data
2 processor. The invention also includes the computer itself when programmed
3 according to the methods and techniques described below.

4 For purposes of illustration, programs and other executable program
5 components such as the operating system are illustrated herein as discrete blocks,
6 although it is recognized that such programs and components reside at various
7 times in different storage components of the computer, and are executed by the
8 data processor(s) of the computer.

9 10 **Exemplary System**

11 Fig. 2 shows an exemplary system 200 in which the inventive
12 methodologies discussed below can be employed. In the discussion immediately
13 below, the system's components are first identified followed by a discussion of
14 their functionality.

15 16 **System Components**

17 In the illustrated example, system 200 comprises a designer component
18 202, a shape/verb generator 204, and an exemplary application 206. One primary
19 focus of system 200 is to provide a way, in an application, to have a very
20 lightweight, fast runtime system that allows for modification of a shape or
21 animation on the fly in the context of the application (which can typically
22 comprise a game).

23 Designer component 202 comprises an external tools module that can
24 include, among other components, modeling/animation systems 210 and
25 shape/motion capture systems 212. The designer component also comprises

1 various shape and verb offline tools 214 that comprise an abstract space definition
2 module 216 and an example position module 218 that positions examples in
3 abstract space.

4 Application 206 comprises a shape/verb runtime system 220 that is
5 embedded in an application, such as a game, that uses the system described below
6 to drive the animation of a character. The inventive aspects that are about to be
7 described pertain to the shape and verb offline tools 214, shape/verb generator
8 204, and the shape/verb runtime system 220.

9 10 **System Component Functionality**

11 Typically, a designer relies on external modeling and animation systems
12 and/or geometry and motion capture technology (external tools 208) to create
13 initial forms and motions. In the context of this document, these initial forms and
14 motions are referred to as example forms and example motions, or simply
15 “examples”. As an illustration, consider an object that has a shape. One way of
16 capturing the object’s shape might be to project structured light onto the object so
17 that a camera and computer can record the object’s shape. This shape is digitized
18 and can then be used in graphics applications. For a situation that involves
19 motion, a person might be outfitted with a number of reflectors and then filmed so
20 that a computer can capture their motion. In each of the these systems, once the
21 images are captured they are very difficult to modify. In a traditional system,
22 these captured images from externals tools 208 would flow directly to an
23 application that would simply pull out the captured images and run them as
24 appropriate in known ways.
25

1 In the illustrated and described embodiment, shape and verb offline tools
2 214 enable the designer to organize these example forms or motions that serve as
3 input into shape and verb generator 204. To do so, the designer can choose a set
4 of adjectives that characterize the forms or a set of adverbs that characterize the
5 motions. The adjectives or adverbs define an abstract space and each adjective or
6 adverb represents a separate axis in this abstract space. For instance, adjectives
7 that describe the form of a human arm may include gender, age, and elbow bend.
8 These adjectives are used to define the axes in an abstract space.

9 Consider Fig. 3, for example. There, each of the adjectives is seen to define
10 an axis in the abstract space. The adjective "gender" can range in values from
11 male to female; the adjective "age" can range in values from old to young; and the
12 adjective "elbow bend" can range in value from no bend to full bend. These axes
13 are of interest because the form of a human arm changes depending on whether it
14 belongs to a male or female, or whether the person is old or young. The arm also
15 deforms when the skeleton bends. In the latter case, deformation does not refer to
16 the rigid body transformations induced by, for instance, bending the elbow, but
17 rather the more subtle non-rigid changes in muscles and skin.

18 Adverbs for a walk may include the walker's mood and aspects of the
19 environment in which the walk takes place. A happy walk is quite different from a
20 sad or angry walk. Walks also differ with the slope or the surface walked on.

21 Once the designer has defined the abstract space using shape and verb
22 offline tools 214 (Fig. 2), each example form or motion is annotated with its
23 location in the abstract space. Annotation of an example's location in the abstract
24 space is a mathematical characterization of the example's location. In addition,
25 motion examples can be tagged with so-called keytimes, such as the moment when

1 each foot touches the ground. The keytimes provide a means to perform automatic
2 time warping at runtime. Details of the time warping can be found in Rose et al,
3 *Verbs and Adverbs: Multidimensional motion interpolation*, IEEE Computer
4 Graphics and Applications 18, 5 (Sept. 1998), pps. 32-40.

5 Based on the annotated examples and the abstract space, shape and verb
6 generator 204 solves for the coefficients of a smoothly-varying interpolation of the
7 forms and motions across the abstract space. These coefficients provide the means
8 to interpolate between the example forms and motions at runtime. In the context
9 of this document, the output produced by the shape and verb generator 204 is
10 referred to as a "shape" when interpolating forms, and as a "verb" when
11 interpolating motions.

12 At runtime, application 206 chooses, at each moment in time, desired
13 values for the adjectives or adverbs, thus defining a specific location in the
14 abstract space. For instance, a character can be set to be happy or sad or anywhere
15 in between; an arm can be specified to be more male or female, or to respond to
16 the bending of the elbow. The shape and verb runtime system 220 then responds
17 to the selected location in the abstract space by efficiently blending the annotated
18 examples to produce an interpolated form or motion.

19 The number of adverbs or adjectives defines the dimension of the abstract
20 space. In this document, D is used to denote the dimension. The number of
21 examples included in a construction of a shape or verb are denoted by N . Each
22 motion in a verb as well as each form in a shape is required to have the same
23 structure. That is, all forms in a shape must have the same number of vertices with
24 the same connectivity. Since example forms must all have the same topological
25 structure, we do not need to address the correspondence problem here. Examples

must each define the same set of DOFs, but may do so in a variety of ways. Different curve representations, number of control points, etc., can all coexist within a single set of examples. All example motions in a particular verb must also represent the same action. A set of example walks, for instance, must all start out on the same foot, take the same number of steps, and have the same arm swing phase. Thus, all examples (forms or motions) must have the same number of degrees of freedom (DOFs). The number of DOFs, denoted M , equals three times the number of vertices in a form (for the x,y,z coordinates). In the case of a motion, the number of DOFs is the number of joint trajectories times the number of control points per curve.

In the discussion that follows, a number of different symbols are used to mathematically describe and illustrate the inventive approach. The table just below summarizes or explains these symbols.

Object	Variable	Subscript	Range
<i>Example</i>	X	i	1...N
DOF	x	i	1...N
		j	1...M
Point in Adverb Space	\mathbf{p}	i	
Radial basis	R	i	
Radial Coefficient	r	i, j	
Linear Basis	A	l	0...D
Linear Coefficient	a	i, l	
Distance	d	i	

1
2 Consider that an example is a collection of numbers that numerically
3 describe the DOFs. For instance, a shape is composed of many vertices and
4 triangles. Each vertex can be considered as three numbers and there may be a few
5 hundred vertices that describe a shape. Typically, there may be a few thousand
6 numbers that are associated with each example and that describes the example.
7 With respect to motion, such is analogously described by a collection of numbers
8 that might define, for example, the motion of an arm during a defined period of
9 time. An example is denoted mathematically as X_i , where:

10
11
$$X_i = \{x_{ij}, \mathbf{p}_i, K_m : i = 1 \dots N, j = 1 \dots M, m = 0 \dots \text{NumKeyTimes}\}$$

12
13 Each x_{ij} , the j^{th} DOF for the i^{th} example represents a coordinate of a vertex
14 or, in the case of a motion, a uniform cubic B-spline curve control point. \mathbf{p}_i is the
15 location in the abstract space assigned to the example. K is the set of keytimes
16 that describe the phrasing (relative timing of the structural elements) of the
17 example in the case of a motion. Based on the keytime annotations for each
18 motion example, the curves are all time-warped into a common generic time
19 frame. Keytimes are, in essence, additional DOFs and are interpolated at runtime
20 to undo the time-warp. See Rose et al., referenced above, for details on the use of
21 keytimes.

22 23 **Shape and Verb Generation**

24 Given a set of examples (i.e. shapes or motions), the challenge is to
25 ascertain mathematically how a non-example shape or motion is going to look.

1 Recall that the non-example shape or motion constitutes a shape or motion that
2 was not defined by a designer. In the illustrated and described embodiment, a set
3 of weights is developed for a particular point in the abstract space. The particular
4 point represents a point that is not an example and for which a shape or motion is
5 to be derived. The set of weights for that point consists of a weight value for each
6 example. The individual weight values are then blended together to define the
7 shape or motion at the given point.

8 Fig. 4 is a flow diagram that describes steps in a method in accordance with
9 the described embodiment. The method can be implemented in any suitable
10 hardware, software, firmware, or combination thereof. In the illustrated example,
11 the method is illustrated in software. Step 400 provides a point in an abstract
12 space for which a form or motion is to be defined. The abstract space is populated
13 with examples, as described above. Step 402 develops a set of weights or weight
14 values for that particular point based upon the predefined examples that populate
15 the abstract space. That is, for each example, a weight value is derived. Step 404
16 then combines the individual weights and their corresponding examples to define a
17 shape or motion for the point of interest. In the illustrated and described
18 embodiment, each weight value is used to adjust all of the corresponding
19 coefficients of an example that define that example. This constitutes an
20 improvement over past methods, as will be described in more detail below.

21 That is, given a set of examples, a continuous interpolation over the abstract
22 space is generated for the shape or verb. The goal is to produce, at any point \mathbf{p} in
23 the abstract space, a new motion or form $X(\mathbf{p})$ that is derived through interpolation
24 of the examples. When \mathbf{p} is equal to the position \mathbf{p}_i for a particular example i , then
25

1 $X(\mathbf{p})$ should equal X_i . In between the examples, smooth intuitive changes should
2 take place.

3 In Rose et al., referenced above, each B-spline coefficient was treated as a
4 separate interpolation problem (e.g. 1200 separate problems in their walk verb)
5 which leads to inefficiencies. In the illustrated and described embodiment, a
6 cardinal basis is developed where one basis function is associated with each
7 example. As a cardinal basis, each basis function has a value of 1 at the example
8 location in the abstract space and a value of 0 at all other example locations. This
9 specification guarantees an exact interpolation. For each DOF, the bases are
10 simply scaled by the DOF values and then summed.
11 This approach is more efficient than the approach set forth in Rose et al. in the
12 case of animations and, the approach can be applied to shape interpolation.

13 Fig. 5 is a flow diagram that describes steps in a method in accordance with
14 the described embodiment. The steps can be implemented in any suitable
15 hardware, software, firmware, or combination thereof. In the illustrated example,
16 the steps are implemented in software. Step 500 provides a plurality of examples.
17 These examples can be generated by designers as described above. Step 502
18 develops a cardinal basis where one basis function is associated with each
19 example. Step 504 then interpolates to find a point in abstract space that is a
20 blended combination of each of the examples provided in step 500.

21 One specific example of how this can be done is described below. It will
22 be appreciated that the specific example constitutes but one way of implementing
23 the described embodiment. Other ways of implementing the described
24 embodiment can be used without departing from the spirit and scope of the
25 claimed subject matter.

Selecting Cardinal Basis Function Shapes

In the illustrated example, a specific shape of the individual cardinal basis functions is selected. In the present situation, the problem is essentially one of scattered data interpolation, as we have few data points, the examples, in a relatively high dimensional space. Most published scattered data interpolation methods focus on one and two-dimensional problems. Linear interpolation using Delauney triangulation, for instance, does not scale well in high dimensions. Based on the present need to work in high dimensions with very sparse samples, an approach is adopted which is a combination of radial basis functions and low order (linear) polynomials.

For a given point in abstract space, the defined cardinal basis gives the weight values for each of the examples that are to be used to define the shape or motion for the point in abstract space. The specific cardinal basis that was used in experimentation has the form:

$$w_{i_1}(\mathbf{p}) = \sum_{i_2=1}^N r_{i_2 i_1} R_{i_2}(\mathbf{p}) + \sum_{l=0}^D a_{i_1 l} A_l(\mathbf{p})$$

Equation 1

where $r_{i_2 i_1}$ and R_{i_2} are, respectively, the radial basis function weights and radial basis functions themselves, and the $a_{i_1 l}$ and A_l are the linear coefficients and linear bases. The subscripts i_1 and i_2 both indicate example indices. Given these bases, the value of each DOF is computed at runtime based on the momentary location, \mathbf{p} , in the abstract space. The value of each DOF, x_j , at location (\mathbf{p}) is, thus, given by:

$$x_j(\mathbf{p}) = \sum_{i=1}^N w_i(\mathbf{p}) x_{i,j}$$

Equation 2

The equation directly above constitutes a weighted sum of all of the examples for each DOF at a location \mathbf{p} . This weighted sum provides the shape or motion of the point in abstract space for which an example does not exist. In the past, methods have not calculated a single weight for each example. Rather, individual weights for each of the coefficients that describe a single example were calculated. Where there are many examples, this computational load is quite burdensome and results in a very slow evaluation that is not suitable for runtime animation. Here, however, a single weight is calculated for each example and then applied to the coefficients that define that example. The modified examples are then combined to provide the resultant shape or motion. This approach is advantageous in that it is much faster and is readily suited for runtime animation. Examples of experimental results are given below that demonstrate how the inventive systems and methods improve on past techniques.

The linear function in the above approach provides an overall approximation to the space defined by the examples, and permits extrapolation outside the convex hull of the locations of the examples, as will be understood by those of skill in the art. The radial bases locally adjust the solution to exactly interpolate the examples. The linear approximation and the radial bases are discussed below in more detail.

Simple One Dimensional Example

1 Before exploring in detail the derivation of the cardinal basis, a simple one
2 dimensional example is given to assist the reader in envisioning the derivation that
3 is described below.

4 Consider Fig. 6 which is a graph of a function where the x -axis represents a
5 continuum of all of the possible positions in abstract space and the y axis
6 represents the value of a weight w_I . Consider also that there are five examples (Ex
7 1 – Ex 5) that have been defined such that, for any point in abstract space we wish
8 to derive a set of weights (w_I - w_5) such that a combination of the weights yields a
9 blended new example that is a realistic representation of any point in the abstract
10 space. The goal of the derivation of the cardinal basis is that the basis function or
11 weight has a value of 1 at the example location and 0 at all other example
12 locations.

13 Here, notice that the x axis is labeled with five points (Ex 1, Ex 2, Ex 3, Ex
14 4, and Ex 5). These points constitute the five defined example locations in the
15 abstract space. Notice that the weight value w_I for each of these points is 1 for
16 example 1 (Ex 1) and 0 for all of the other examples. A point of interest can be
17 envisioned as sliding back and forth along the x axis and as it does so, its weight
18 coefficient w_I will change in accordance with the function that is defined for w_I .
19 With respect to this function, we know that it will have a value of 1 at the point
20 that corresponds to Example 1 and will be 0 elsewhere. What we do not know,
21 however, is the shape of the function at the places between the points that
22 correspond to the examples. This is something that is derived using Equation 1
23 above.

24 Equation 1 is essentially an equation that represents a sum of two different
25 parts—a radial basis part (the term on the left side of the equation) and a linear

1 part (the term on the right side of the equation). The weight function for an
2 example at some point \mathbf{p} is equal to the summed weighted radial basis functions
3 and the summed linear basis. The linear basis is essentially a plane equation for a
4 plane in the abstract space. For a 4-dimensional space, the equation would be a
5 hyperplane, 3-dimensional space, the equation would be a plane, for a 2-
6 dimensional space, the equation would be a line.

7 In the discussion just below, the section entitled "Linear Approximation"
8 describes characteristics of the linear portion of equation 1 and the section entitled
9 "Radial Basis" describes characteristics of the radial basis portion of equation 1.

10 11 **Linear Approximation**

12 In the illustrated example, we first would like to form the best (in the least
13 squares sense) linear approximation for each DOF based on the examples given
14 for that DOF. In other words, we would like to find the hyperplane through the
15 abstract space that comes closest to approximating the example values of that
16 DOF. This defines M separate least squares problems, one for each DOF variable.
17 However, since each example places all variables at a single location, \mathbf{p} , we can
18 instead determine a set of N hyperplanes, one for each example, that form a basis
19 for the M hyperplanes. The basis hyperplanes are derived by fitting a least squares
20 hyperplane to the case where one example has a value of 1 and the rest have a
21 value of 0.

22 Consider the following:

$$23 \quad \mathbf{p}_h \mathbf{a} = \mathbf{F},$$

24 where \mathbf{p}_h is a matrix of homogeneous points in the abstract space (i.e., each
25 row is a point location followed by a 1), \mathbf{a} are the unknown linear coefficients, and

1 \mathbf{F} is a *Fit* matrix expressing the values we would like the linear approximation to
2 fit. In this case, \mathbf{F} is simply the identity matrix since we are constructing a
3 cardinal basis. Later, \mathbf{F} will take on a slightly different structure as we discuss
4 reparameterization of the abstract space (see "Reparameterization" section below).

5 Fig. 7 shows the linear approximation A_1 , and three exemplary radial basis
6 functions associated with three different examples for a simple one-dimensional
7 abstract space. The three examples are located at $p = 0.15, 0.30, 0.75$. The straight
8 line labeled A_1 is the line that fits best through $(0.15, 1), (0.30, 0), (0.75, 0)$. A
9 "best fit" hyperplane for any particular DOF could then be evaluated by simply
10 scaling the bases by the DOF values and summing.

11 In the Fig. 7 example, the R_x terms represent the basic shape of the radial
12 basis function. The lowercase "r" associated with each linear basis function
13 represents an amount by which the basis function is scaled in the vertical direction.
14 The width of the basis functions, in this example, is implied by the distance to the
15 nearest other example. For instance, p_1 and p_2 are close to one another and
16 constitute the closest examples relative to the other. In this particular example, the
17 width of the radial parts of the function is four times the distance to the nearest
18 example. Hence, the width of p_1 and p_2 are the same, only shifted relative to one
19 another. The width for example p_3 is much larger because it is further away from
20 its nearest example (p_2). Fig. 7 simply illustrates an example of equation 1 above.

22 Radial Basis

23 Radial basis interpolation is known and is discussed in Micchelli,
24 *Interpolation of scattered data: Distance matrices and conditionally positive*
25 *definite functions*, Constructive Approximation 2 (1986), and in a survey article

Powell, *Radial basis functions for multivariable interpolation: A review*, Algorithms for Approximation, J.C. Mason and M.G. Cox, Eds. Oxford University Press, Oxford UK, 1987, pps. 143-167. Radial basis functions have been used in computer graphics for image warping as described in Ruprecht et al., *Image warping with scattered data interpolation*, IEEE Computer Graphics And Applications 15, 2 (Mar. 1995), 37-43; Arad et al., *Image warping by radial basis functions: Applications to facial expressions*, Computer Vision, Graphics, and Image Processing 56, 2 (Mar. 1994), 161-172; and for 3D interpolation as described in Turk et al., *Shape transformation using variational implicit functions*, Computer Graphics (Aug. 1999), pps. 335-342 (Proceedings of SIGGRAPH 1999).

Given the linear approximation described above, there still remain residuals between the example values x_{ij} and the scaled and summed hyperplanes. To account for the residuals, one solution might be to associate a radial basis with each DOF, as described in Rose et al mentioned above. Instead, we proceed as before and use the radial bases to account for the residuals in the cardinal bases. The residuals in the cardinal bases are given by:

$$q_{i1i2} = \delta_{i1i2} - \sum_{l=1}^D a_{l2l} A_l(\mathbf{p}_{i1}), \text{ where } \delta_{ij} = \begin{cases} 1 & \text{when } i=j \\ 0 & \text{otherwise} \end{cases}$$

To account for these residuals, we associate N radial basis functions with each example. Since there are N examples, we, thus, need N^2 radial basis functions. We solve for the weights of each radial bases, r_{i2i1} , to account for the residuals such that, when the weighted radial bases are summed with the hyperplanes, they complete the cardinal bases.

1 This leaves the issue of choosing the specific shape of the radial bases and
2 determining the radial coefficients. Radial basis functions have the form:

$$R_i(d_i(\mathbf{p}))$$

3
4
5 where R_i is the radial basis associated with X_i and $d_i(\mathbf{p})$ is a measure of the
6 distance between \mathbf{p} and \mathbf{p}_i , most often the Euclidean norm $\|\mathbf{p} - \mathbf{p}_i\|$. There are a
7 number of choices for this basis. Rose et al., referenced above, chose a basis with
8 a cross section of a cubic B-spline centered on the example, and with radius twice
9 the Euclidean distance to the nearest other example. Turk et al., referenced above,
10 selected the basis:

$$R(d) = d^2 \log(|d|)$$

11
12
13
14 as this generates the smoothest (thin plate) interpolations. In the described
15 embodiment, both bases were tried. Bases with the B-spline cross-section were
16 found to have compact support, thus, outside their support, the cardinal bases are
17 simply equal to the linear approximation. They therefore extrapolate better than
18 the smoother, but not compact, radial basis functions used by Turk et al.
19 Accordingly, we chose to use the B-spline bases for this extrapolation property.

20 The radial bases weights, $r_{i_2 i_1}$, can now be found by solving the matrix
21 system:

$$\mathbf{Q}\mathbf{r} = \mathbf{q}$$

22
23
24 where \mathbf{r} is an $N \times N$ matrix of the unknown radial bases weights and is
25 defined by the radial bases such that, $Q_{i_2 i_1} = R_{i_2}(p_{i_1})$ the value of the unscaled radial

1 basis function centered on example i_2 at the location of example i_1 . The diagonal
2 terms are all $2/3$ since this is the value of the generic cubic B-spline at its center.
3 Many of the off diagonal terms are zero since the B-spline cross-sections drop to
4 zero at twice the distance to the nearest example.

5 Referring back to Fig. 7, three radial basis functions are seen to be
6 associated with the first of the three examples. If these three radial basis functions
7 are summed with the linear approximation, we get the first cardinal basis, the line
8 labeled w_1 in Fig. 8. Note that the first cardinal basis passes through 1 at the
9 location of the first example, and is 0 at the other example locations. The same is
10 true for the other two cardinal bases w_2 and w_3 .

11 Given the solutions for the radial basis weights, we now have all the values
12 needed to evaluate equations 1 and 2 at runtime. The line designated $\sum wx$ in Fig.
13 8 is simply the three cardinal bases scaled by the example values and summed as
14 in equation 2.

15 16 **Shape and Verb Runtime System**

17 At runtime, an application selects a point of interest in the abstract space.
18 This point may move continuously from moment to moment, if for instance, a
19 character's mood changes or the character begins to walk up or downhill. The
20 shape and verb runtime system 220 (Fig. 2) takes this point and generates an
21 interpolated form or motion and delivers it to the application for display.

22 23 **Complexity Issues**

24 The runtime complexity of the formulation in equations 1 and 2 is
25

$$MN + N(N + S) = MN + N^2 + NS$$

where M is the number of DOF variables, N is the number of examples, and S is the dimension plus one of the abstract space. In Rose et al., referenced above, there was a separate linear hyperplane and radial basis per DOF (approximately 1200 B-spline coefficients in their walking verb). The complexity in their formulation is given by:

$$M(N + S) = MN + MS$$

In our formulation above there is only one set of linear bases and one set of radial bases per example. The efficiency is gained due to the fact that there are many fewer examples than DOF variables. For instance, if $M = 1200$, $N = 10$, and $S = 6$, then the comparison is $MN + N^2 + NS = 12,160$ vs. $MN + MS + N^2 = 19,200$. Due to some additional constants, the efficiencies are actually a bit better. We have implemented both Rose et al.'s formulation and the one presented here and found an approximate increase in speed at a factor of about 2 in most cases.

Reparameterization and Modification of Shapes and Verbs

Once a shape or verb has been generated, the abstract space can be quickly explored to see the interpolated forms and motions. It is possible that some of the regions in this space are not entirely to the designer's liking. For instance, Fig. 9 shows a 2D space of interpolations of a simple three-dimensional shape. Blue forms indicate examples and grey forms are the result of the shape and verb runtime system 220 (Fig. 2).

Problem regions can be seen in each of the two upper corners. Both corners exhibit cracks due to surface interpenetration. Another type of problem

1 can occur when an interpolation changes more quickly than desired in one region
2 and more slowly than desired in a neighboring region. For instance, at the point in
3 the abstract space that is half way between a happy walk and a sad walk, the
4 character may appear to be more sad than happy, rather than neutral.

5 Two methods are typically available to modify the results produced by the
6 shape and verb generator 204 (Fig. 2). In one method, a new example can be
7 inserted at the problem location and a new verb or shape generated. A quick way
8 to bootstrap this process is to use the undesirable results at the problem location as
9 a “starting point”, fix up the offending vertices or motion details, and reinsert this
10 into the abstract space as a new example. In the second method, the designer first
11 selects an acceptable interpolated form or motion from a location in the abstract
12 space near the problem region. Next, the designer moves this form to a location in
13 the problem region. This relocated form will be treated exactly the same as an
14 example. This relocated form is referred to as a “pseudo-example” in this
15 document.

16 Going back to the problem with the walk verb described above, a neutral
17 walk cycle found elsewhere in the abstract space may be moved to the half way
18 point between happy and sad walks.

19 The place from which the pseudo-example is taken will be point p . We
20 denote the new position to which it is moved to as \tilde{p} . The pseudo-example is not
21 a “true” example as it is a linear sum of other examples. However, it acts like an
22 example in terms of changing the shape of the radial basis functions. In essence,
23 this method reparameterizes the abstract space. Reparameterization is very
24 effective in producing shapes of linked figures, as we demonstrate later with a
25 human arm shape.

Fig. 10 shows this technique applied to the 2D space of 3D forms. The space has been reparameterized with two pseudo-examples shown in red. Arrows indicate the locations from which the pseudo-examples were drawn.

Creating the reparameterized verb or shape proceeds much as before. We introduce a few new notations, however, before we formalize the reparameterization approach. We have already mentioned $\tilde{\mathbf{p}}$, the new location of the pseudo-examples. $\tilde{\mathbf{p}}$ also includes the real example locations during reparameterization. We, furthermore, use a tilde to denote the new radial basis weights, \tilde{r} , the new linear coefficients \tilde{a} , and the new cardinal bases \tilde{w} . We also denote the total number of real and pseudo-examples as \tilde{N} .

As before, the form or motion at any point in the abstract space is:

$$x_j(\mathbf{p}) = \sum_{i_1=1}^{\tilde{N}} \tilde{w}_{i_1}(\mathbf{p}) x_{i_1,j}$$

Equation 3

Note that the interpolated form or motion still only includes a sum over the real examples. In other words, there are still only N cardinal bases after the reparameterization. The pseudo-examples reshape these N bases from w to \tilde{w} .

$$\tilde{w}_{i_1}(\mathbf{p}) = \sum_{i_2=1}^{\tilde{N}} \tilde{r}_{i_2 i_1} R_{i_2}(\mathbf{p}) + \sum_{l=0}^D \tilde{a}_{i_1 l} A_l(\mathbf{p})$$

Equation 4

Also as before $\tilde{\mathbf{p}}_h \tilde{\mathbf{a}} = \tilde{\mathbf{F}}$. However, $\tilde{\mathbf{F}}$ is no longer an identity matrix. It now has \tilde{N} rows and N columns. Assuming the new pseudo-examples are all located at the bottom of the matrix, the top $N \times N$ square is still an identity. The

lower $\tilde{N} - N$ rows are the values of the original cardinal bases w at the location where the pseudo-examples were taken from (see equation 4). That is, in each row, the *Fit* matrix contains the desired values of the N cardinal bases, now at \tilde{N} locations. These are 1 or 0 for the real example locations and the original cardinal weights for the pseudo-examples.

The radial portion of the cardinal basis construction proceeds similarly. The residuals are now:

$$\tilde{q}_{i_1 i_2} = \tilde{F}_{i_1 i_2} - \sum_{l=0}^D \tilde{a}_{i_2 l} A_l(\mathbf{p}_{i_1})$$

Note that instead of the Kronecker delta, we now have the values from \tilde{F} .

The coefficients, $\tilde{r}_{i_2 i_1}$, are now found by solving the matrix system,

$$Q\tilde{r} = \tilde{q}$$

As before, $Q_{i_1 i_2}$ has terms equal to $R_{i_2}(\tilde{p}_{i_1})$, however, these terms now include the new pseudo-example locations. As a consequence, the radii of the radial basis functions may change.

Fig. 11 is a flow diagram that describes steps in a reparameterization method in accordance with the described embodiment. Step 1100 defines a set of examples that pertain to a form or motion that is to be animated. The examples are provided relative to a multi-dimensional abstract space. In the illustrated example, this step can be implemented by a animation designer using a set of software tools to design, for instance, example objects or character motions. Step 1102 examines a plurality of forms or motions that are animated with the abstract space from the defined set of examples. In the illustrated and described

embodiment, the forms or motions can be animated from the examples using the techniques described above. Step 1104 then identifies at least one form or motion that is undesirable. This step can be manually performed, e.g. by the designer physically examining the animated forms or motions, or it can be performed by software that looks for undesirable forms or motions. An example of an undesirable form or motion is one that, for example, exhibits undesirable characteristics such as surface interpenetration due to interpolation issues. Once the undesirable forms or motions are identified, step 1106 selects a form or motion from a location within the abstract space that is proximate a location that corresponds to the undesirable form or motion. This step can be implemented by a designer actually physically selecting the form or motion. Alternately, it can be performed by software. Once the form or motion is selected, step 1108 replaces the undesirable form or motion with the selected form or motion to provide a pseudo-example that constitutes a linear sum of the original examples. Processing as far as subsequent rendering operations can take place as described above.

Shapes and Skeletons

Animated characters are often represented as an articulated skeleton of links connected by joints. Geometry is associated with each link and moves with the link as the joints are rotated.

If the geometry associated with the links is represented as rigid bodies, these parts of the character will separate and interpenetrate when a joint is rotated. A standard way to create a continuous skinned model is to smoothly blend the joint transforms associated with each link of the character. This is supported in

1 current graphics hardware, making it an attractive technique. This simple method
2 exhibits some problems, however.

3 We use an arm bending at the elbow to discuss the problems associated
4 with transform blending and to demonstrate how we can overcome these
5 difficulties in the context of shape blending.

6 To perform the simple transform blending, a blending weight α is assigned
7 to each vertex. For instance, for the elbow bending, vertices sufficiently below the
8 elbow would have weight $\alpha = 1$, and those sufficiently above, $\alpha = 0$. Those
9 vertices near the elbow would have α values between 0 and 1, as will be
10 understood by those of skill in the art.

11 We denote the transformation matrix for the upper arm as T_0 , and the
12 transformation for the lower arm as T_1 . We use superscripts to denote the amount
13 of rotation of the joint. Thus, as the elbow rotates, we say that T_1 changes from
14 T_1^0 when the elbow is straight to T_1^1 at a bent position. In between, the transform
15 is T_1^β for a bending amount β . We refer to the position of the arm when $T_1 = T_1^0$
16 as the rest position.

17 We denote the position of a vertex as x_0 when the transformation of the
18 joint is T_1^0 . The simple transform blending is defined as:

$$x = \alpha T_1^\beta x_0 + (1-\alpha) T_0 x_0$$

21 where α is the blending weight assigned to that vertex. Unfortunately,
22 linearly summed transformation matrices do not behave as one would like. The
23 result is that the skin appears to shrink near the rotating joint (see Fig. 12). In
24 addition, simple transform blending does not provide a rich set of tools for
25 creating effects such as a muscle bulging as the elbow bends.

In the illustrated and described embodiment, we provide solutions to both problems through the use of our inventive shape blending techniques. To do this, the designer first creates examples of a straight arm, $X_{\beta=0}$, and a bent arm, $X_{\beta=1}$, for, say, a 90-degree bend (Fig. 11). The bent arm includes any muscle bulging or other deformations the designer wants to include. We obviously cannot simply perform a direct geometric blend between these forms because at 45 degrees, the lower arm would have shrunk considerably, since the chord from the fingertip of the bent arm to the fingertip of the straight arm passes nearer to the elbow than an arc would, as will be appreciated by those of skill in the art.

Instead, what we would like is a combination of transform blending and shape blending. Accordingly, we call the vertex on the bent arm, corresponding to x_0 on the arm in the rest position, x^1 . As in the simple blended transforms, we also have a blending weight, α , associated with each vertex. We now seek a second arm in the rest position with a corresponding vertex, x_0^1 , such that when it is subjected to the simple transform blending at an angle of $\beta=1$ it will exactly match the bent arm specified by the designer. Thus,

$$x^1 = \alpha T_1^{\beta=1} x_0^1 + (1 - \alpha) T_0 x_0^1$$

Now we can solve for the vertices of this new arm in the rest position (see Fig. 13):

$$x_0^1 = (\alpha T_1^{\beta=1} + (1 - \alpha) T_0)^{-1} x^1$$

Equation 5

1 We can now first perform a geometric blend of the new arm in the rest
2 position with the original arm in the rest position and then transform it. The result
3 is:

$$x_{\beta} = (\alpha T_1^{\beta} + (1 - \alpha)T_0)(\beta x_0^1 + (1 - \beta)x_0)$$

4
5
6 Equation 6
7

8 This geometric blend followed by the blended transform will match the
9 original arm geometry when $\beta=0$ and will match the bent arm created by the
10 designer when $\beta=1$.

11 The arm model discussed above contains only two example forms, the arm
12 in the rest position and the bent arm. It will be appreciated, however, that all of
13 the techniques discussed above can be used to perform a multi-way blend of the
14 articulated geometry. First, all example forms are untransformed to the rest
15 position via equation 5. Then the multi-way shape blending is applied to the
16 untransformed forms. Finally, the blending result is transformed in the normal
17 way. In other words, the interpolation of the forms in the rest position simply
18 replaces the latter half of equation 6.

19 Fig. 14 shows the straight arm example one, of 6 examples in this shape.
20 The results above the straight arm are the result of naively blending transforms on
21 this one example. On the bottom right is a blend of the 6 examples untransformed
22 to the rest position. Finally, this strange blended form is pushed through the
23 blended transformation to give the result shown in the upper right.

24 Fig. 15 is a flow diagram that describes step in a animation method in
25 accordance with the described embodiment. Step 1500 defines examples forms in

1 different positions. In the illustrated, a first example form is defined in a first
2 position and a second example form is defined in a second position. Step 1502
3 then computes a form in the first position such that when the computed form is
4 subjected to a transform blending operation that places the computed form in the
5 second position, it will match the second example form. Step 1504 geometrically
6 blends the computed form in the first position with the first example form in the
7 first position to provide a geometrically blended form in the first position.
8 Specific examples of this are given above. Step 1506 then transform blends the
9 geometrically blended form to provide a form that matches the second example
10 form in the second position.

11 **Results**

12
13 We have applied the paradigm described above to a number of shapes and
14 linked-figure animations. We will discuss two of each. All performance statistics
15 measure raw interpolation speeds and do not include time to render. All timings
16 were gathered on a 450 Mhz Pentium II, Dell Precision 610- machine.

17 **Simple Shapes**

18
19 The shape demonstrated in Fig. 10 includes 5 example forms, each
20 consisting of 642 vertices and 1280 faces. Blending in this space can be done at
21 5500 frames per second (fps). One step of Loop subdivision is applied to this
22 mesh and the limit positions and normals are computed. This results in a mesh
23 with 2562 vertices and 5120 faces that is rendered at runtime. A two dimensional
24 abstract space was created with the horizontal axis being "bend" and the vertical
25 being "thickness." The initial space had regions in the upper right and left corners

1 where the blended surface was interpenetrating. This space was reparameterized
2 by adding pseudo-examples near these locations that were not interpenetrating.
3 When real examples were added instead, the blending slowed down to around
4 4000 fps.

6 **Arm**

7 The arm was created by modifying Viewpoint models inside 3D-
8 Studio/Max. The arm example has an underlying skeleton that has 3 rotational
9 degrees of freedom - one for the shoulder, elbow and wrist. We have a fourth
10 variable for the parameterized arm, gender. The abstract space has 8 real
11 examples (straight arm, shoulder up, shoulder down and elbow bent for male and
12 female models), and 6 pseudo-examples which are mostly placed to smooth out
13 bulges where the shrinking from blended transforms was being overcompensated.
14 These examples have 1335 vertices and 2608 faces each. This dataset can be
15 interpolated at 2074 fps.

16 Fig. 16 is a visualization of a 2D space of arms with 4 real examples and 1
17 pseudo-example. Elbow bend is parameterized along the horizontal axis and
18 gender along the vertical. Extrapolation can produce some interesting results, as
19 are indicated.

21 **Animation**

22 We constructed parameterized motions, verbs, for two different characters:
23 a human figure named Stan and a robot warrior. While both bipedal, each moves
24 in very different ways.

1 Stan moves in a humanlike, though often exaggerated, manner, while the
2 robot warrior moves very mechanically. Our technique had no trouble
3 encompassing both forms. Our motion examples were chosen to encompass
4 emotional states such as mopiness, cockiness, fear, anger, and for physical
5 parameters such as damage and surface slope.

6 The verbs shown in Figs. 17-19 were constructed from a mix of motion
7 capture and hand animated source. The motion capture data was gathered
8 optically. The hand-animated source was generated on two popular software
9 animation packages: 3D-Studio/Max for the robot, and Maya for some of Stan's
10 data. This data is applied to a skeleton positioned with a translation at the root and
11 a hierarchy of Euler angle joints internally. A technique similar to one discussed
12 in Bodenheimer, et. al., *The process of motion capture: Dealing with the data*,
13 *Proceedings of the Eurographics Workshop on Computer Animation and*
14 *Simulation* (Sept. 1997), pps. 3-18, ensured that the angles remained well-
15 behaved.

16 Our robot warrior has 60 degrees of freedom. Our robot data exhibits two
17 primary kinds of variation: slope of walking surface and level of damage to the
18 robot. Damage results in limping and slope causes the character to rotate the
19 joints in the leg, foot, and waist, and shift weight to accommodate.

20 Fig. 17 shows a sampling of the robot walking verb. Green boxed figures
21 are examples. The others are interpolations and extrapolations. The vertical axis
22 shows robot health and the horizontal axis surface slope. Fig. 19 shows the robots
23 in the center column of Fig. 17 rotated to the side to better show the character
24 limping. We constructed a number of robot verbs: powered-down idle, power-up,
25 powered-up idle, power-down, idle-to-walk, walk, and walk-to-idle. These verbs,

1 together with a transitioning mechanism can be combined to form a verb graph
2 such as discussed in Rose, et. al., referenced above. The robot verbs evaluate at
3 9700 fps in the absence of rendering. Thus, a robot evaluated using verbs can be
4 run at 30 fps with only a 0.3% percent processor budget.

5 We also constructed a walking verb from a human figure, Stan, with 138
6 degrees of freedom. We chose 3 emotional axes for this verb which seemed to
7 encompass the gamut of variation present in the data. These were happy-to-sad,
8 knowledgeable-to-clueless, and low-to-high-energy. Our example motions exhibit
9 these subjective characteristics: easy-going, mopey, cocky, goofy, angry, afraid,
10 and neutral. Fig. 18 shows a sampling of our walk along the knowledge and
11 happiness axes. Unlike the robot data, which was designed to fall at regular places
12 in the adverb plane, our Stan motions are less regular. As there are no restrictions
13 upon example placement, we are able to construct verbs with irregular example
14 placement, as shown by the green-boxed figures. Evaluating a pose for Stan is
15 extremely efficient: 3900 fps or a 0.7% processor budget at 30 fps.

16 Conclusions

17 Shape and motion interpolation has been shown to be an effective and
18 highly efficient way of altering shape and motion for real-time applications such
19 as computer games. The front-end solution process is also efficient, (a fraction of
20 a second), so a tight coupling between artist, solver, and interpolator provides a
21 new way for an artist to work without fundamentally altering their workflow.
22 With our system, artists can more easily extend their work into the interactive
23 domain.
24

1 In the context of skeleton based figures, we are able to combine both shape
2 blending with blended transforms to create a smoothly skinned character. We are
3 able to overcome the limitations of blended transforms, while including the artist's
4 input for how muscles deform as the skeleton moves, and still maintain interactive
5 performance.

6 Although the invention has been described in language specific to structural
7 features and/or methodological steps, it is to be understood that the invention
8 defined in the appended claims is not necessarily limited to the specific features or
9 steps described. Rather, the specific features and steps are disclosed as preferred
10 forms of implementing the claimed invention.
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25

1 **CLAIMS**

2 1. An blending method comprising:

3 providing a set of examples that pertain to a shape or motion that is to be
4 animated, the examples being provided relative to a multi-dimensional abstract
5 space;

6 selecting a point within the multi-dimensional abstract space that does not
7 coincide with a point that is associated with any of the examples, the selected
8 point corresponding to a shape or motion within the abstract space;

9 computing a single weight value for each of the examples; and

10 combining the single weight values for each of the examples in a manner
11 that defines an interpolated shape or motion that is a blended combination of each
12 of the examples of the set of examples.

13
14 2. The blending method of claim 1, wherein said selecting is performed
15 by an application.

16
17 3. The blending method of claim 1, wherein said selecting is performed
18 by a game application.

19
20 4. The blending method of claim 1, wherein said selecting is performed
21 at run time.

22
23 5. The blending method of claim 1, wherein said computing is
24 performed at run time.

1 6. The blending method of claim 1, wherein said computing and
2 combining are performed at run time.

3
4 7. The blending method of claim 1, wherein said computing comprises:
5 defining a cardinal basis for each example; and
6 evaluating the cardinal basis for each example relative to the selected point
7 to provide the weight value.

8
9 8. The blending method of claim 7, wherein the cardinal basis
10 comprises:
11 a radial basis function portion; and
12 another portion that is different from the radial basis function portion.

13
14 9. The blending method of claim 8, wherein said another portion is not a
15 radial basis function portion.

16
17 10. The blending method of claim 8, wherein said another portion is a
18 linear portion.

19
20 11. One or more computer-readable media having computer-readable
21 instructions thereon which, when executed by a computer, implement the method
22 of claim 1.

1 **12.** A computerized blending system that is programmed with
2 instructions which, when executed by the system, implement the method of claim
3 1.

4
5 **13.** An blending method comprising:
6 linearly approximating a degree of freedom that is associated with a new
7 form or motion that is to be rendered based upon a plurality of examples that
8 define respective forms or motions within an abstract space;
9 defining a radial basis function for each of the examples;
10 combining the linear approximation and the radial basis functions to
11 provide a cardinal basis function; and
12 using the cardinal basis function to render the new form or motion.

13
14 **14.** The blending method of claim 13, wherein:
15 said acts of linearly approximating and said defining are performed for each
16 example; and
17 said combining comprises combining each of the respective linear
18 approximations and their associated radial basis functions to provide multiple
19 cardinal basis functions, one for each example; and
20 said using comprises combining the multiple cardinal basis functions to
21 define a function that describes the new form or shape within the abstract space.

22
23 **15.** The blending method of claim 13, wherein said defining comprises
24 scaling the radial basis function for each example.
25

1 **16.** The blending method of claim 15, wherein said scaling comprises
2 evaluating a matrix system to ascertain a plurality of scaling weights, individual
3 weights of which are used to scale the radial basis functions.
4

5 **17.** The blending method of claim 16, wherein said matrix system is
6 configured so that its evaluation yields scaling weights which, when used to scale
7 a corresponding radial basis functions, result in a combination of the radial basis
8 functions and the linear approximation to provide the cardinal basis function.
9

10 **18.** The blending method of claim 13, wherein the radial basis functions
11 are selected from a b-spline family of radial basis functions.
12

13 **19.** The blending method of claim 13, wherein said linearly
14 approximating comprises approximating the degree of freedom with a least
15 squares linear approximation.
16

17 **20.** One or more computer-readable media having computer-readable
18 instructions thereon which, when executed by a computer, implement the method
19 of claim 13.
20

21 **21.** A computerized blending system that is programmed with
22 instructions which, when executed by the system, implement the method of claim
23 13.
24
25

1 **22.** One or more computer-readable media having computer-readable
2 instructions thereon which, when executed by a computer, cause the computer to:

3 linearly approximate a degree of freedom that is associated with a new form
4 or motion that is to be rendered based upon a plurality of examples that define
5 respective forms or motions within an abstract space, by deriving basis
6 hyperplanes that fit a least squares hyperplane to a case where one example has a
7 value of 1 and the remaining examples have values of 0;

8 account for residuals between the example values and the hyperplane by:

9 associating a radial basis function with each example;

10 ascertaining a radial basis weight value for each radial basis
11 function; and

12 scaling each radial basis function by its ascertained radial basis
13 weight value; and

14 sum the linear approximation and scaled radial basis functions to provide a
15 cardinal basis function.

16
17 **23.** The computer-readable media of claim 22, wherein the instructions
18 cause the computer to perform the recited acts of linear approximation,
19 accounting, and summing for each example to provide multiple cardinal basis
20 functions.

21
22 **24.** The computer-readable media of claim 23, wherein the instructions
23 further cause the computer to sum the multiple cardinal basis functions to provide
24 a function that describes the new form or motion within the abstract space.

1 **25.** The computer-readable media of claim 24, wherein the instructions
2 cause the computer to select a point on the defined function and render a new form
3 or motion.

4
5 **26.** The computer-readable media of claim 22, wherein each radial basis
6 function has a width that is a function of the distance between its associated
7 example and the next nearest example in abstract space.

8
9 **27.** The computer-readable media of claim 22, wherein each radial basis
10 function is selected from the b-spline family of radial basis functions.

11
12 **28.** A computerized blending system comprising:
13 at least one computer-readable media;
14 at least one processor;
15 instructions resident on the computer-readable media which, when executed
16 by the processor, cause the blending system to:

17 linearly approximate a degree of freedom that is associated with a
18 new form or motion that is to be rendered based upon a plurality of examples that
19 define respective forms or motions within an abstract space, by deriving basis
20 hyperplanes that fit a least squares hyperplane to a case where one example has a
21 value of 1 and the remaining examples have values of 0;

22 account for residuals between the example values and the hyperplane by:

23 associating a radial basis function with each example;

24 ascertaining a radial basis weight value for each radial basis
25 function; and

1 scaling each radial basis function by its ascertained radial basis
2 weight value; and

3 sum the linear approximation and scaled radial basis functions to provide a
4 cardinal basis function.
5

6 **29.** The computerized blending system of claim 28, wherein the
7 instructions cause the blending system to perform the recited acts of linear
8 approximation, accounting, and summing for each example to provide multiple
9 cardinal basis functions.
10

11 **30.** The computerized blending system of claim 29, wherein the
12 instructions further cause the blending system to sum the cardinal basis functions
13 to provide a function that describes the new form or motion within the abstract
14 space.
15

16 **31.** The computerized blending system of claim 30, wherein the
17 instructions cause the blending system to select a point on the defined function and
18 render a new form or motion.
19

20 **32.** The computerized blending system of claim 28, wherein each radial
21 basis function has a width that is a function of the distance between its associated
22 example and the next nearest example in abstract space.
23
24
25

1 **33.** The computerized blending system of claim 28, wherein each radial
2 basis function is selected from the b-spline family of radial basis functions.

3
4 **34.** An blending method comprising:
5 defining a set of examples that pertain to a form or motion that is to be
6 animated, the examples being provided relative to a multi-dimensional abstract
7 space;

8 examining a plurality of forms or motions that are animated within the
9 abstract space from the defined set of examples;

10 identifying at least one form or motion that is undesirable;

11 selecting a form or motion from a location within the abstract space that is
12 proximate a location that corresponds to the undesirable form or motion; and

13 replacing the undesirable form or motion with the selected form or motion
14 to provide a pseudo-example that constitutes a linear sum of the examples of the
15 set of examples.

16
17 **35.** The blending method of claim 34 further comprising, prior to said
18 examining, providing the plurality of forms or motions by, for each form or
19 motion:

20 linearly approximating a degree of freedom that is associated with a new
21 form or motion that is to be rendered based upon the set of examples;

22 defining a radial basis function for each of the examples;

23 combining the linear approximation and the radial basis functions to
24 provide a cardinal basis function; and

25 using the cardinal basis function to render the new form or motion.

1
2 **36.** The blending method of claim 35, wherein:
3 said acts of linearly approximating and said defining are performed for each
4 example; and
5 said combining comprises combining each of the respective linear
6 approximations and their associated radial basis functions to provide multiple
7 cardinal basis functions, one for each example; and
8 said using comprises combining the multiple cardinal basis functions to
9 define a function that describes the new form or shape within the abstract space.
10

11 **37.** The blending method of claim 36, wherein the radial basis functions
12 are selected from a b-spline family of radial basis functions.
13

14 **38.** The blending method of claim 37 further comprising, after said
15 replacing producing a plurality of new forms or motions by repeating said acts of
16 linearly approximating a degree of freedom, defining a radial basis function,
17 combining and using, the pseudo-examples influencing the shape of the cardinal
18 basis functions.
19

20 **39.** An blending method comprising:
21 defining at least two examples of a form, a first of the example forms being
22 defined in a first position and a second of the example forms being defined in a
23 second position that is different from the first position; and
24
25

1 computing a form in the first position such that when the computed form is
2 subjected to a transform blending operation that places the computed form in the
3 second position, it will match the second example form.

4
5 **40.** The blending method of claim 39, wherein the first position is a rest
6 position.

7
8 **41.** The blending method of claim 39, wherein the first position is a rest
9 position and the second position is angularly displaced from the first position.

10
11 **42.** The blending method of claim 39, wherein said computing
12 comprises computing a plurality of vertices associated with the form.

13
14 **43.** The blending method of claim 42 further comprising, after
15 computing the plurality of vertices, geometrically blending the computed form in
16 the first position with the first example form in the first position to provide a
17 geometrically blended form in the first position.

18
19 **44.** The blending method of claim 43 further comprising after said
20 geometrically blending, transform blending the geometrically blended form to
21 provide the form that matches the second example form.

22
23 **45.** The blending method of claim 39, wherein the example forms
24 pertain to a skeleton-based figure.


1 46. One of more computer-readable media having computer-readable
2 instructions thereon which, when executed by a computer, cause the computer to:

3 define at least two examples of a form, a first of the example forms being
4 defined in a first position and a second of the example forms being defined in a
5 second position that is different from the first position; and

6 compute a form in the first position such that when the computed form is
7 subjected to a transform blending operation that places the computed form in the
8 second position, it will match the second example form.

ABSTRACT

Modern animation and modeling systems enable artists to create high-quality content, but provide limited support for interactive applications. Although complex forms and motions can be constructed either by hand or with motion or geometry capture technologies, once they are created, they are difficult to modify, particularly at runtime. Interpolation provides a way to leverage artist-generated source material. Presented here are methodologies for efficient runtime interpolation between multiple forms or multiple motion segments. Radial basis functions provide key mathematical support for the interpolation. Once the illustrated and described system is provided with example forms and motions, it generates a continuous range of forms referred to as a “shape” or a continuous range of motions referred to as a verb. Additionally, shape interpolation methodology is applied to articulated figures to create smoothly skinned figures that deform in natural ways. The runtime interpolation of the forms or motions runs fast enough to be used in interactive applications such as games.






Fig. 2






Fig. 3

*Fig. 4**Fig. 5*

*Fig. 6*




Fig. 8




Fig. 7




Fig. 10




Fig. 9


Fig. 11



Fig. 12




Fig. 13





Fig. 14

Fig. 15






Fig. 16

00012200 244200000




Fig. 17




Fig. 18




Fig. 19

